

02-RF-01873

FINAL

2001 ANNUAL ROCKY FLATS CLEANUP AGREEMENT

(RFCA)

GROUNDWATER MONITORING REPORT

for the

Rocky Flats Environmental Technology Site

November 2002

TABLE OF CONTENTS

| | |
|--|------|
| EXECUTIVE SUMMARY | viii |
| 1.0 INTRODUCTION | 1-1 |
| 1.1 Site Description | 1-1 |
| 1.2 Geology and Hydrogeology | 1-2 |
| 1.2.1 Introduction..... | 1-2 |
| 1.2.2 Stratigraphy..... | 1-2 |
| 1.2.2.1 Rocky Flats Alluvium..... | 1-2 |
| 1.2.2.2 Other Surficial Deposits..... | 1-3 |
| 1.2.2.3 Arapahoe Formation | 1-3 |
| 1.2.2.4 Laramie Formation and Fox Hills Sandstone..... | 1-3 |
| 1.2.2.5 Pierre Formation | 1-4 |
| 1.2.3 Geologic Structure | 1-4 |
| 1.2.4 Hydrogeology | 1-4 |
| 1.2.4.1 Definition of the Uppermost Aquifer for the Site | 1-5 |
| 1.2.4.2 Groundwater Occurrence and Distribution | 1-5 |
| 1.2.4.3 Groundwater Flow | 1-6 |
| 1.2.4.4 Hydraulic Conductivity..... | 1-7 |
| 1.3 Environmental History..... | 1-8 |
| 1.3.1 Rocky Flats Cleanup Agreement | 1-9 |
| 1.3.2 Integrated Monitoring Plan for Groundwater | 1-9 |
| 1.3.3 Changes to the Groundwater Monitoring Program | 1-18 |
| 2.0 DATA SUMMARY FOR RFCA-DESIGNATED WELLS SAMPLED IN 2001 | 2-1 |
| 2.1 Data Screening..... | 2-1 |
| 2.2 Values Above Tier I and Tier II Action Level Criteria..... | 2-3 |
| 2.2.1 Boundary Wells | 2-3 |
| 2.2.2 Drainage Wells | 2-3 |
| 2.2.3 Plume Definition Wells | 2-4 |
| 2.2.4 Plume Extent Wells | 2-7 |
| 3.0 GROUNDWATER FLOW CONDITIONS DURING 2001 | 3-1 |
| 3.1 Potentiometric Surface Maps..... | 3-1 |
| 3.2 Average Linear Flow Velocities | 3-3 |
| 3.3 Well Hydrographs and Water Level Change Maps | 3-6 |
| 3.4 Real Time Groundwater Monitoring Network..... | 3-9 |
| 4.0 PERFORMANCE MONITORING | 4-1 |
| 4.1 Mound Plume..... | 4-1 |
| 4.1.1 Mound Site Source Removal | 4-1 |
| 4.1.2 Mound Plume/SW059 Remediation System..... | 4-9 |
| 4.2 Solar Ponds Nitrate/Uranium Plume..... | 4-18 |

| | | |
|---------|---|------|
| 4.3 | East Trenches Plume..... | 4-24 |
| 4.3.1 | Trenches T3 and T4 Source Removal..... | 4-24 |
| 4.3.2 | B-Ponds/East Trenches Plume..... | 4-45 |
| 4.4 | 881 Hillside French Drain..... | 4-49 |
| 4.5 | Ryans Pit Source Removal..... | 4-58 |
| 5.0 | BUILDING D&D MONITORING THROUGH 2001..... | 5-1 |
| 5.1 | Building 123..... | 5-3 |
| 5.2 | Building 444..... | 5-6 |
| 5.3 | Building 771..... | 5-9 |
| 5.3.1 | Bowman’s Pond Groundwater Characterization..... | 5-12 |
| 5.4 | Building 886..... | 5-13 |
| 5.5 | Building 779..... | 5-15 |
| 5.6 | Building 707..... | 5-19 |
| 5.7 | Building 776/777..... | 5-21 |
| 5.8 | Buildings 371/374..... | 5-24 |
| 5.9 | Building 865..... | 5-26 |
| 5.10 | Building 883..... | 5-28 |
| 5.11 | Building 881..... | 5-30 |
| 5.12 | Building 991..... | 5-32 |
| 5.13 | Building 559..... | 5-34 |
| 6.0 | PRESENT SANITARY LANDFILL – 2001 UPDATE..... | 6-1 |
| 6.1 | Operating History of the Present Sanitary Landfill..... | 6-1 |
| 6.2 | Summary of Previous Investigations..... | 6-2 |
| 6.3 | Current Groundwater Monitoring Program..... | 6-3 |
| 6.4 | Physical Characteristics of the Groundwater System..... | 6-5 |
| 6.4.1 | Description of the “Uppermost Aquifer”..... | 6-5 |
| 6.4.2 | Potentiometric Surface..... | 6-6 |
| 6.4.3 | Vertical Hydraulic Gradients..... | 6-7 |
| 6.4.4 | Average Linear Groundwater-Flow Velocities..... | 6-7 |
| 6.5 | Groundwater Quality at the Present Sanitary Landfill..... | 6-8 |
| 6.5.1 | Spatial Distribution of Groundwater Constituents..... | 6-8 |
| 6.5.1.1 | Upgradient Wells..... | 6-8 |
| 6.5.1.2 | Downgradient Wells..... | 6-9 |
| 6.5.2 | Statistical Evaluation of Groundwater Constituents..... | 6-10 |
| 6.5.3 | Trend Plots and Data Interpretation..... | 6-13 |
| 6.6 | Conclusions..... | 6-15 |
| 7.0 | PLUME DEGRADATION MONITORING..... | 7-1 |
| 7.1 | Plume Degradation..... | 7-1 |
| 7.1.1 | Electron Donors..... | 7-1 |

| | | |
|---------|---|------|
| 7.1.2 | Electron Acceptors..... | 7-2 |
| 7.1.3 | Metabolic By-Products | 7-2 |
| 7.2 | Carbon Tetrachloride Plume (IHSS 118.1)..... | 7-2 |
| 7.2.1 | Electron Donors | 7-6 |
| 7.2.2 | Electron Acceptors..... | 7-6 |
| 7.2.3 | Metabolic By-Products | 7-7 |
| 7.2.4 | Conclusions and Recommendations | 7-9 |
| 7.3 | 903 Pad/Ryan’s Pit Plume | 7-10 |
| 7.3.1 | Electron Donors | 7-12 |
| 7.3.2 | Electron Acceptors..... | 7-12 |
| 7.3.3 | Metabolic By-Products | 7-14 |
| 7.3.4 | Conclusions and Recommendations | 7-15 |
| 7.4 | PU&D Yard Plume Investigations..... | 7-16 |
| 7.4.1 | Electron Donors | 7-17 |
| 7.4.2 | Electron Acceptors..... | 7-18 |
| 7.4.3 | Metabolic By-Products | 7-19 |
| 7.4.4 | Conclusions and Recommendations | 7-21 |
| 7.4.5 | PU&D Yard Plume Treatability Study | 7-21 |
| 7.4.5.1 | Project Events | 7-22 |
| 7.4.5.2 | Treatment Effectiveness..... | 7-22 |
| 7.4.5.3 | Conclusions and Work Planned | 7-26 |
| 8.0 | GROUNDWATER EVALUATIONS | 8-1 |
| 8.1 | Groundwater ICP/MS Sampling Project..... | 8-1 |
| 8.2 | Industrial Area Plume Investigation | 8-3 |
| 8.2.1 | Industrial Area Plume Investigation Results..... | 8-3 |
| 8.3 | Discussion of Volatile Organic Compound and Nitrate Plumes..... | 8-7 |
| 8.3.1 | Composite VOC Plumes..... | 8-7 |
| 8.3.2 | Methodology Used in the 2001 Annual Report | 8-8 |
| 8.3.3 | Discussion of VOC Plumes | 8-10 |
| 8.3.3.1 | Industrial Area Plume | 8-10 |
| 8.3.3.2 | OU2 Plume | 8-15 |
| 8.3.3.3 | PU&D Yard/Present Sanitary Landfill Plume | 8-18 |
| 8.3.3.4 | Other Small VOC Plumes and Point Sources | 8-19 |
| 8.3.4 | Recommendations..... | 8-19 |
| 8.3.5 | Nitrate Plumes | 8-21 |
| 9.0 | GROUNDWATER CHARACTERIZATION ACTIVITIES | 9-1 |
| 9.1 | Actinide Migration..... | 9-1 |
| 9.1.1 | Introduction..... | 9-1 |
| 9.1.2 | Background..... | 9-1 |
| 9.1.3 | Methodology for Quantifying Actinide Transport..... | 9-2 |
| 9.1.4 | Plutonium and Americium in Shallow Groundwater..... | 9-3 |
| 9.1.5 | Uranium in Shallow Groundwater | 9-4 |
| 9.1.6 | Summary of Groundwater Pathway Analysis | 9-4 |
| 9.2 | Site-Wide Water Balance..... | 9-5 |
| 9.2.1 | Introduction and Objectives..... | 9-5 |
| 9.2.2 | General Approach and Conceptual Flow Model..... | 9-6 |
| 9.2.3 | Numerical Model Approach and Design | 9-7 |
| 9.2.4 | Model Performance and Scenario Evaluations | 9-8 |

| | | |
|--------|---|-------|
| 9.2.5 | Implications to Site Closure and Potential Applications..... | 9-9 |
| 9.3 | Current Solar Ponds Plume Investigation | 9-10 |
| 9.3.1 | Description of Investigation..... | 9-10 |
| 9.3.2 | Data Handling | 9-12 |
| 9.3.3 | Results and Discussion | 9-14 |
| 9.3.4 | Recommendations..... | 9-17 |
| 10.0 | OTHER GROUNDWATER PROGRAM ACTIVITIES | 10-1 |
| 10.1 | Well Abandonment and Installation | 10-1 |
| 10.2 | Potential Residential Use of Shallow Groundwater at RFETS | 10-2 |
| 10.3 | Evaluation of Mining Potential at RFETS | 10-9 |
| 11.0 | GROUNDWATER DATA QUALITY ASSESSMENT FOR 2001 | 11-1 |
| 11.1 | General Sampling Summary | 11-1 |
| 11.2 | Quality Control Assessment | 11-1 |
| 11.2.1 | Quality Control Samples..... | 11-2 |
| 11.2.2 | PARCC Parameters..... | 11-2 |
| 11.3 | Discussion of Analyte Groups | 11-6 |
| 11.3.1 | Metals | 11-6 |
| 11.3.2 | Radonuclides..... | 11-10 |
| 11.3.3 | Volatile Organic Compounds and Dissolved Gases | 11-12 |
| 11.3.4 | Water Quality Parameters | 11-15 |
| 11.3.5 | Polychlorinated Biphenyls | 11-17 |
| 12.0 | CONCLUSIONS AND FUTURE ACTIVITIES..... | 12-1 |
| 13.0 | REFERENCES..... | 13-1 |